

RESEARCH ARTICLE

Open Access



Defining novel plant polyamine oxidase subfamilies through molecular modeling and sequence analysis

Cesar Daniel Bordenave¹, Carolina Granados Mendoza², Juan Francisco Jiménez Bremont³, Andrés Gárriz¹ and Andrés Alberto Rodríguez^{2*}

Abstract

Background: The polyamine oxidases (PAOs) catabolize the oxidative deamination of the polyamines (PAs) spermine (Spm) and spermidine (Spd). Most of the phylogenetic studies performed to analyze the plant PAO family took into account only a limited number and/or taxonomic representation of plant PAOs sequences.

Results: Here, we constructed a plant PAO protein sequence database and identified four subfamilies. Subfamily PAO back conversion 1 (PAObc1) was present on every lineage included in these analyses, suggesting that BC-type PAOs might play an important role in plants, despite its precise function is unknown. Subfamily PAObc2 was exclusively present in vascular plants, suggesting that t-Spm oxidase activity might play an important role in the development of the vascular system. The only terminal catabolism (TC) PAO subfamily (subfamily PAOtc) was lost in Superasterids but it was present in all other land plants. This indicated that the TC-type reactions are fundamental for land plants and that their function could be taken over by other enzymes in Superasterids. Subfamily PAObc3 was the result of a gene duplication event preceding Angiosperm diversification, followed by a gene extinction in Monocots. Differential conserved protein motifs were found for each subfamily of plant PAOs. The automatic assignment using these motifs was found to be comparable to the assignment by rough clustering performed on this work.

Conclusions: The results presented in this work revealed that plant PAO family is bigger than previously conceived. Also, they delineate important background information for future specific structure-function and evolutionary investigations and lay a foundation for the deeper characterization of each plant PAO subfamily.

Keywords: Evolution, Phylogeny, Polyamine oxidase, Polyamine catabolism, Protein structure, Homology modeling

Background

PAOs are amino oxidases involved in polyamine metabolism. This group of enzymes catalyzes the oxidation of free higher PAs such as Spm and Spd, and their acetylated derivatives at their secondary amino groups through two known reaction modes [1]. Thus, PAOs acting in the TC of PAs oxidize the carbon on the *endo*-side of the N₅ of Spm or Spd producing 1,3-diaminopropane (DAP), H₂O₂, and the respective aldehydes [2]. In turn, PAOs functioning in the BC pathway oxidize the carbon on the *endo*-side of the N₅ of Spm and Spd rendering

Spd and putrescine (Put), respectively, as well as 3-aminopropanal and H₂O₂ [2]. Put, Spd and Spm are the most abundant free PAs in plants [3], and the oxidation of these amines have been associated with numerous events related to cell growth and development, biotic and abiotic stress responses [4–8].

Plant PAOs show a great heterogeneity in terms of reaction mode, substrates, products and subcellular localization [9–19]. However, the current knowledge about aspects of plant PAOs is limited to enzymes from a few model plant species like *Z. maize*, *A. thaliana*, *O. sativa*, *G. hirsutum* and *B. distachyon* [9–21]. On the other hand, whereas three PAO protein crystal structures are available at the PDB database, only one of them represents the plant kingdom: the maize apoplasmic

* Correspondence: andresrodriguez@conicet.gov.ar

²Departamento de Botánica, Instituto de Biología, Universidad Nacional Autónoma de México, Apartado Postal 70-367, Coyoacán, 04510 México City, Mexico

Full list of author information is available at the end of the article



TC-type PAO1 (ZmPAO1) [22–25]. The other two PAO crystals structures belong to the *S. cerevisiae* BC-type PAO (FMS1) [26] and the *M. musculus* N1-acetyl PA oxidase (MmAPAO) [21, 27]. Although ZmPAO1 has been used as template to model the structure of mammalian PAOs [28], molecular-modeling structure analysis of plant PAOs are scarce [29, 30].

The first aim of the present work was to build a protein sequence database, through a domain architecture analysis strategy [31], in order to investigate the evolutionary relationships among plant PAOs including an ample taxonomic representation of the main angiosperm lineages. The second aim was to analyze the structural features and the conservation of the amino acids involved in the active site of plant PAOs. In order to do this, we performed an analysis of protein structures obtained by molecular modeling using the available crystal structures of PAOs. Our results showed that the plant PAO family is composed of at least four subfamilies with distinct evolutionary relationships, structural and functional features. In addition, their analysis allowed us to identify the amino acids potentially involved in the enzymatic mechanism.

Results

Sequence database construction through a domain architecture approach

The election of the remote-homology detection method is an important factor when searching for plant PAOs sequences, since the majority of the known members of this group show low sequence identity (Additional file 1 Table S1). In this trend, the Pfam database, a domain architecture HMM-based database [32], is probably the most appropriate source of sequences. Therefore, we searched the Pfam database for domains representing amino oxidase enzymes.

Domain architecture analysis revealed the presence of a single copy of the *Amino_oxidase* domain (PF01593) and the absence of other domains in any of the sequences analyzed (Additional file 1 Figure S1). After filtering the sequences, the database comprised 543 sequences from 46 angiosperm species (17 monocot and 29 eudicot species, and *Amborella*) and 124 sequences from early divergent green plants (the Chlorophytes *Chlorella variabilis*, *Micromonas pusilla* and *Chlamydomonas reinhardtii*, the Charophyta *Klebsormidium nitens*, the Bryophyta *Physcomitrella patens*, the Lycopodiophyta *Selaginella moellendorffii*, the Monilophyta *Azolla filiculoides* and the Gymnosperm *Araucaria cunninghamii*).

Clustering of the sequence database

Sequences were clustered using a distance method (UPGMA) and sequences from green plants species were classified into thirteen clades (Fig. 1; Additional file 1 Table S2). A new set of alignments within each clade showed that

each of them comprehended a unique group of homologous sequences.

Clade I contained 31 sequences from eudicots species, including the sequences of *A. thaliana* PAO1 (AtPAO1) and *G. hirsutum* PAO5 (GhPAO5), both BC-type PAOs [10, 17]. Clade II was almost exclusively composed of genes from monocots species (34 sequences from monocots out of 37 total sequences), including the sequences of the apoplastic enzymes ZmPAO1 and *O. sativa* PAO6 (OsPAO6) [18, 22, 33]. Even though ZmPAO1 is a well-documented TC-type PAO [20], OsPAO6 reaction mode has not yet been determined. Clade III showed 34 sequences from eudicots species, including the sequence of *A. thaliana* PAO5 (AtPAO5), a cytoplasmic BC-type PAO [14]. Clade IV included 134 sequences, 81 from eudicots and 53 from monocots species. Among these sequences were found BC-type PAOs such as *A. thaliana* PAOs 2 to 4 (AtPAO2, AtPAO3, AtPAO4), *O. sativa* PAOs 3 to 5 (OsPAO3, OsPAO4, OsPAO5) and *B. distachyon* PAOs 2 and 3 (BdPAO2, and BdPAO3) [11, 13, 19, 34, 35]. Interestingly, AtPAO2, AtPAO3, AtPAO4, OsPAO3, OsPAO4 and OsPAO5 were reported as peroxisomal enzymes [11, 13, 35]. Clade V was composed of seven sequences from monocots species, including the cytoplasmic BC-type PAO *O. sativa* PAO1 (OsPAO1) [15]. Clades I to V did not include any sequences of proteins previously reported and characterized as non PAO enzymes. At last, Clades VI to XIII did not include any sequence belonging to enzymes with reported PAO activity, however some of these sequences were previously reported and characterized as non PAO enzymes (Fig. 1). Features of the well-documented PAOs within each clade were overviewed in Table 1.

Although there are differences in the subcellular localization between known PAOs of different clades (Table 1), the results of the prediction of subcellular localization were not consistent and therefore they were not included as a classification criteria (Additional file 1: Table S3).

Protein structure homology-modeling of plant PAOs

The protein sequences of all clades were modeled with the three available PAO crystal structures. ZmPAO1 resulted in the best template for Clades I and II, whereas members of Clades III to V were best modeled with MmAPAO. In turn, low quality models were obtained with the sequences included in Clades VI to XIII. Therefore, these results suggested that only the clades I to V belong to plant PAO subfamilies.

Sequences of clades I to V were then compared to their best templates. Despite the variation in the inherent quality associated to the models, the structures obtained for each group showed a high consistence and a good percentage of identity in the core of the structures (Fig. 2). However, some of the groups showed portions of the sequences whose structure could not be determined.




Table 1 Known plant PAOs summary table

Name	Clade	UniproKB ID	Reaction mode	Substrate	Products	Subcellular Localization	Bibliography
AtPAO1	1	Q9FNA2	BC	Spm, N1-ac-Spm, Nor-Spm, t-Spm	Spd + H ₂ O ₂	Cytoplasmic	[10, 34, 35]
GhPAO5	1	IDL7VGD5	BC	Spm	Spd + H ₂ O ₂	–	[17]
ZmPAO1	2	O64411	TC	Spd, Spm	DAP + H ₂ O ₂	Apoplasmic	[22, 23, 33, 36]
OsPAO6	2	Q0J291	–	–	–	Apoplasmic	[18]
OsPAO7	2	Q0J290	TC	Spd, Spm, N1-Ac-PAs	DAP + H ₂ O ₂	Apoplasmic	[16]
AtPAO5	3	Q9SU79	BC	t-Spm, Spd, Spm, N1-Ac-PAs	Spd/Put + H ₂ O ₂	Cytoplasmic	[14]
AtPAO2	4	Q9SKX5	BC	Spd, Spm, N1-Ac-PAs, tSpm, Nor-Spm	Spd/Put + H ₂ O ₂	Peroxisomal	[11, 34, 35]
AtPAO3	4	Q9LYT1	BC	Spd, Spm, N1-Ac-PAs, tSpm, Nor-Spm	Spd/Put + H ₂ O ₂	Peroxisomal	[11, 34, 35]
AtPAO4	4	Q8H191	BC	Spd, Spm, tSpm	Spd/Put + H ₂ O ₂	Peroxisomal	[11, 34, 35]
BdPAO2	4	I1J1Z5	BC	Spd, Spm, N1-Ac-PAs, tSpm	Spd/Put + H ₂ O ₂	–	[19]
BdPAO3	4	I1J380	BC	Spm	Spd + H ₂ O ₂	–	[19]
OsPAO3	4	Q7X809	BC	Spd, Spm, Nor-Spm	Spd/Put + H ₂ O ₂	Peroxisomal	[13]
OsPAO4	4	Q7XR46	BC	Spd, Spm, Nor-Spm	Spd + H ₂ O ₂	Peroxisomal	[13]
OsPAO5	4	Q0J954	BC	Spd, Spm, Nor-Spm	Spd + H ₂ O ₂	Peroxisomal	[13]
OsPAO1	5	Q5NAI7	BC	tSpm, Spm, N1-Ac-Spm, Nor-Spm	Spd + H ₂ O ₂	Cytoplasmic	[15]

The conservation of key amino acids at the active site was studied and compared among the clades (Table 2 and Additional file 1 Table S4). Most of the amino acids that constitute the active site were highly conserved within each group, and all the plant PAO subfamilies displayed the conservation of a lysine at the position of the residue Lys300 of ZmPAO1, which forms the catalytically essential structural motif Lys-H₂O-FAD [25, 36]. In addition, Glu60 of ZmPAO1 is also present in all members of clade II, whereas those of clades III and IV exhibited a His in the same position, and clades I and V displayed the conservation of the non-polar side chain amino acids Ala and Gln, respectively. Interestingly, Glu60 of ZmPAO1 has been considered one of the most relevant amino acids in terms of interaction with the substrate, and it is substituted by His in MmAPAO, FMS1 and mammalian spermine oxidase (MmSMO) [24, 25, 36, 37].

The ZmPAO1 enzyme shows a Phe residue (Phe401) that is positioned parallel to a Tyr (Tyr437), both flanking the catalytic tunnel on opposite sides. These residues are thought to define a kind of *aromatic sandwich* around the substrate [37]. Our analysis showed that aromatic residues were conserved in these positions in clades I and II, but were absent in the other subfamilies (Table 2).

Plant PAO subfamilies phylogenetic distribution

Plant PAO subfamilies showed a distinct phylogenetic distribution as a result of gene duplication and extinction events. Gymnosperms proteomes are still poorly documented, therefore no extinction event was hypothesized for these lineages.

Our results indicate that clade IV conform a plant PAO subfamily, here after referred as PAObc1. This subfamily is

present in all the main lineages of Streptophytes (including Gymnosperms), and that a gene duplication even (both copies with BS > 85) occurred along with the Angiosperms origin (Fig. 3a and b and Fig. 4a). A second subfamily, PAOtc (formerly referred as clade II), arose before the embryophytes diversification, subsequently having at least one gene extinction event in Superasterids (Fig. 3c and Fig. 4b). Clade I, here after subfamily PAObc3, is the result of a gene duplication event preceding Angiosperm diversification (BS > 85), followed by a gene extinction in Monocots (Fig. 3c and Fig. 4b). Subfamily PAObc2, comprehending clades III and V, is exclusively present in single copy in vascular plants (except Gymnosperms, but see above).

Identification of motifs in plant PAOs subfamilies

Differential conserved protein motifs were found for each subfamily of plant PAOs (Table 3). A random subset of sequences from every group was scanned against the differential conserved motifs and the results were contrasted with the phylogenetic tree localization. All the sequences were assigned to the specific plant PAO subfamily using this approach (Table 4).

Recently, some authors reported protein sequences from cotton and flax, characterized as plant PAOs in silico [17, 38]. These sequences were scanned against the differential conserved motifs being most of them (13 out of 16 sequences) assigned to a unique plant PAO subfamily (Table 4). This procedure was also carried out with the sequences of two well-documented plant PAOs that had not been considered in our previous analysis. *O. sativa* PAO7 (OsPAO7) protein [16], which was not included as its sequence did not pass the selection criteria (it had less than five amino acids before the start of




Fig. 2 Protein structure of plant PAOs subfamilies. Protein structures were obtained by molecular modeling against the appropriate template. ZmPAO1 and MmAPAO templates showed on top colored by secondary structure, (a) and (d) respectively. Each picture shows an overlap of the structures within each group of sequences. The color represents percentage of identity. (b) Clade I. (c) Clade II. (e) Clade III. (f) Clade IV. (g) Clade V

Table 2 Plant PAOs active site analysis

ZmPAO1 ^a	Tyr437	Phe401	Glu168	Tyr296	Glu60	Tyr167	Tyr163	Asn232	Lys300
MmAPAO ^a	Thr469	–	Val182	Tyr428	His59	Tyr194	Ser468	Glu179	Lys305
Clade I	Tyr	Tyr	Glu	Tyr	Ala	Phe	Ile	Asn	Lys
Clade II	Tyr	Phe/Tyr	Glu	Tyr	Glu	Tyr	Tyr/Phe	Asn	Lys
Clade III	Thr	–	Tyr	Tyr	His	Tyr	Ser	Gln	Lys
Clade IV	Ser	–	Met/Leu	Tyr	His	Glu	Gly	–	Lys
Clade V	Thr	–	Asp	Tyr	Gln	Tyr	Ser	Glu	Lys

^aZmPAO1 and MmAPAO are included as reference




Fig. 3 Phylogeny of plant PAOs subfamilies. The trees were constructed with maximum likelihood method. Nodes with Bootstrap support ≥ 85 are denoted by an asterisk. Aminoacid under the subfamily names indicates the residue present in the position corresponding to Glu60 of ZmPAO1. (a) Subfamily PAObc1. (b) Subfamilies PAObc2 and PAObc3. (c) Subfamily PAObc2




Fig. 4 (See legend on next page.)

(See figure on previous page.)

Fig. 4 Evolution of plant PAO subfamilies. Grey thick branches correspond to the green plants species tree as recovered by Gitzendanner and collaborators [61]. The black and grey thin branches denotes the gene trees for each plant PAO subfamily. Gene extinction is denoted by an X, whereas ? indicates uncertainty in the actual absence of the subfamilies in Gymnosperms. **(a)** Subfamily PAObc1. **(b)** Subfamily PAOtc and PAObc3. **(c)** Subfamily PAObc2

the *Amino_oxidase* domain) and *C. cinencis* PAO4 (CsPAO4) [39], that was not included as its sequence was not present in the Pfam or UniProtKb databases. These sequences were scanned against the differential conserved motifs, and they were assigned to the plant PAO subfamily 2 and 3, respectively (Table 4).

Discussion

A critical task when constructing a protein database suitable for phylogenetic analysis is the functional and structural characterization of new proteins. This is often inferred on the basis of the sequence similarities to proteins with known structure or function. However, remote-homologues [40] can be difficult to detect when distantly related proteins are analyzed using homologues-assigning methods based on pairwise procedures [41]. In this regard, Hidden Markov model (HMM) based methods have been applied to detect distantly related proteins with better results [40, 41]. In the first part of this work we built a protein sequence database of plant PAOs through a domain architecture analysis strategy using the Pfam database, a domain architecture HMM-based database [32]. Our sequence analysis revealed that all the proteins with reported PAO activity presented a single copy of the *amino_oxidase* domain without the presence of any other additional domain (Additional file 1 Figure S1). Even though proteins with single domains are unusual [42], this feature was useful to perform the sequence search and to establish filter criteria. Moreover, some clades included sequences of proteins previously reported and characterized as non PAO enzymes indicating a possible phylogenetic relation between these enzymes and revealing the versatility of the PAO domain architecture. The sequences in the final database shared the same domain architecture, but they did not define a unique group of homologous sequences. This was in line with the observation that the percentages of identity among some of the well-documented plant PAOs were lower than expected for homologous sequences (Additional file 1 Table S1) [43]. However, the clades detected in this work were constituted by unique groups of homologous sequences. Even though the distance trees constructed with the sequence database showed a similar topology as previous plant PAO phylogenetic studies [13, 15, 16, 34, 44, 45], it is noteworthy that we used a larger sequence database. Therefore, it was possible to build groups that included higher number of sequences and species (an average of 40 sequences and 26 species per clade) and to detect a higher number of clades than previous reports. This suggested that the plant PAO family is

bigger than previously conceived. Although we only considered five of the thirteen clades as part of plant PAO subfamilies, we cannot rule out that other clades constitute subfamilies of these plant enzymes with a structure that cannot be modeled with any of the currently available PAO crystal structures.

We also investigated the evolutionary relationships among plant PAOs. Even though several phylogenetic studies of plant PAOs have been performed [13, 15, 16, 19, 34, 38, 44–47], most of them included only a limited number and/or taxonomic representation of plant PAOs sequences hindering the elucidation of the evolution of this protein family in plants. For this reason, we decided not only to enrich the database in terms of number of protein sequences and structures, but also to increase the taxonomic representation of the main green plant lineages. The breadth of our taxon sampling allowed us to determine the phylogenetic distribution of each plant PAO subfamilies. No plant PAO subfamily was identified for Chlorophyta, however this is most probably due to the ample sequence divergence of this lineage compared to the other green plant lineages. The low gymnosperm sequence count in the database (only four) question the correct representation of Gymnosperm sequences in the database and suggest us to be cautious with the interpretation of the absence of several plant PAO subfamilies in this group. Therefore, as stated before, no extinction event was hypothesized for this plant group. The plant PAObc1 subfamily is ubiquitous in almost all green plants and was most probably present since the ancestral Streptophytes (Fig. 5). The peroxisomal subcellular location reported for some PAObc1 sequences is in agreement with the presence on this subfamily in Charophyta, since they present peroxisomes that are more similar to those of land plants compared to other green algae [48]. The apoplastic subfamily PAOtc is involved on cell wall loosening and stiffening during plant development [5, 7]. A different enzyme or group of enzymes must be replacing this function in Superasterids, like copper-containing amine oxidases (a hypothesis that has been already discussed) [49, 50]. The PAObc2 is known to participate during vascular development and this is in agreement with the presence of this subfamily exclusively in vascular plants (Fig. 5). The gene duplication events that gave rise of both copies of PAObc1 and PAObc3 identified since the early diverged angiosperm *A. trichopoda* suggest that the newly acquired plant PAOs formed part of the new gene content that first

Table 3 Aminoacidic motifs for the identification on plant PAOs subfamilies

	Fitness	Hits (Seqs)	Motif
Subfamily 1	169,4	32 (32)	EFF[IM]YAH[DE][QR]RGY[FY]AT[F]WQxM[DE]NAIH[Y]xGS[DN][IM]LW[TL]V[TTN][DEG][EQ]Sx[HR][IV]E[AN]S[Q]x[DN]x[DE]T[L]M]
Subfamily 2	134,0	37 (37)	TIDEK[IV]x[LP]RWxS[DN]IKR[FY]xG[ST][FY]SNxP[IV]GV[DNS][HR]x[EGQ][FH]Y[DN]x[IL][KRI]APV[Gx(3)]F[Y]x[GT][EG][E]H[x]ST[AEOS]
Subfamily 3	112,8	43 (43)	V[FV]E[AG]G[ADGN]ST[R]AV[GGRI]Vx[ST]x[EQ]F[x]AGS[x(2)][V]ExGATW[IV]xGx(1,2)Gx(1,2)P[IL]V[HY]x[IL]M][AS]x[DEQ]x(3)[FL]
Subfamily 4	125,1	136 (136)	LHG[AV][CGS]x[DE]N[PS][LV][AS]x(2)x(2)Lx[L]Yx[TCGS]x[DG][DN]S[IV][IL][FY][DE]HD[EK]Sx(2)[L][FY][DN]x(2)Gx(2)[V][EPS]


Table 4 Automatic subfamily assignment by aminoacidic motif search

ID	Organism	Assignment by phylogeny	Assignment by motif search
U5G093	<i>P. trichocarpa</i>	Subfamily 1	Subfamily 1
A0A078CR66	<i>B. napus</i>	Subfamily 1	Subfamily 1
M0XC59	<i>H. vulgare</i>	Subfamily 2	Subfamily 2
B8BGH2	<i>O. sativa</i>	Subfamily 2	Subfamily 2
R0F4R6	<i>C. rubella</i>	Subfamily 3	Subfamily 3
A0A087GI24	<i>A. alpina</i>	Subfamily 3	Subfamily 3
C5XI79	<i>S. bicolor</i>	Subfamily 3	Subfamily 3
A0A0D9V4T9	<i>L. perrieri</i>	Subfamily 3	Subfamily 3
R0FMX3	<i>C. rubella</i>	Subfamily 4	Subfamily 4
I1J381	<i>B. distachyon</i>	Subfamily 4	Subfamily 4
Lus10020726	<i>L. usitatissimum</i>	Not Included	No Hit
Lus10005021	<i>L. usitatissimum</i>	Not Included	Subfamily 4
Lus10039599	<i>L. usitatissimum</i>	Not Included	No Hit
Lus10019725	<i>L. usitatissimum</i>	Not Included	No Hit
Gh_A05G0221	<i>G. hirsutum</i>	Not Included	Subfamily 3
Gh_A07G0104	<i>G. hirsutum</i>	Not Included	Subfamily 3
Gh_A08G0331	<i>G. hirsutum</i>	Not Included	Subfamily 4
Gh_A08G0507	<i>G. hirsutum</i>	Not Included	Subfamily 1
Gh_A12G2582	<i>G. hirsutum</i>	Not Included	Subfamily 4
Gh_D05G0300	<i>G. hirsutum</i>	Not Included	Subfamily 3
Gh_D07G2378	<i>G. hirsutum</i>	Not Included	Subfamily 3
Gh_D08G0428	<i>G. hirsutum</i>	Not Included	Subfamily 4
Q0J290	<i>O. sativa</i>	Not Included	Subfamily 2
Cs4g14150.1	<i>C. cinnensis</i>	Not Included	Subfamily 3

appeared in the ancestral angiosperms, possibly as a result of the Zeta (seed plants) and/or Epsilon (angiosperms) genome duplications [51, 52].

To strengthen our study, we also analyzed the structural features and the conservation of the amino acids involved in the active site of plant PAOs. Even though it is plausible that proteins with similar structures share similar functions, the protein structure homology-modeling showed us a discrepancy for the subfamily 1 with regard to this statement. Thus, the best template for this group was the TC-type PAO ZmPAO1. However, all of their well-documented members were characterized as BC-type enzymes (Table 1) [10, 17]. The remaining subfamilies showed an agreement between the reaction mode of its members and the reaction mode of its structure modeling templates. Many reports associated the PAO reaction modes with the presence of particular residues in their active site or in their catalytic tunnels. The TC reaction mode has been related to the presence of Glu in the active site and an *aromatic sandwich* in the catalytic tunnel [36, 37]. In this trend, Glu60 has been largely accepted as one of the more relevant residues for catalysis [36, 37], in terms of interaction

with the substrate or its accommodation within the active site of ZmPAO1, as it forms a hydrogen bond with the N₅ atom of the substrate [44]. The residue in this position in the active site of the BC-Type PAOs was also suspected to be important for the catalysis, but in this case it is substituted by His [26, 28, 39, 47]. In line with this, in the ZmPAO1 active site the residues that compose the *aromatic sandwich* around the substrate have been proposed to be important to define the reaction mode of the enzyme [37]. Glu and the *aromatic sandwich* were presented in the subfamily PAOtc, in its orthologue in *Amborella* and in all the sequences from early divergent green plants related to this clade, in agreement with the reaction mode of their members as well as the template for homology-modeling of this group, ZmPAO1. Moreover, these features were absent in subfamilies PAObc1 and PAObc2, suggesting that the members of these groups are BC-type enzymes. On the other hand, subfamily PAObc3 showed the conservation of the residues that conforms the *aromatic sandwich*, but Ala was conserved in the position corresponding to Glu60. Also its orthologue in *Amborella* presented the *aromatic sandwich* and a basic residue in the position



corresponding to Glu60. These results suggested that the *aromatic sandwich* is a structural feature that is only present in the phylogenetically related subfamilies PAOtc and PAObc3 and more likely unrelated with the reaction mode of the enzyme. The presence of Glu to

interact with the N₅ of the substrate might be a critical factor determining the accommodation of the substrate to be oxidized on the *endo* side of the N₅. Moreover, our results suggested that the presence of either a basic or an uncharged residue might lead to a BC-type PAO

reaction mode. In this regard, Tavladoraki et al. (2011) carried out site-directed mutagenesis experiments on the His that occupies this position in the MmSMO, and they reported that its substitution by Glu leads to enzyme inactivation [28]. It would be of great interest to perform a site-directed mutagenesis experiment on a member of the subfamily PAObc3, such as AtPAO1 or GhPAO5, as they are more structurally similar to ZmPAO1, to unravel the function of this key residue.

When the structural, and catalytic features and the phylogenetic distribution of the plant PAO subfamilies were analyzed together, the following conclusions could be drawn:

a) Subfamily PAObc1 was present on every lineage included in these analyses (Fig. 5) suggesting that BC-type PAOs might play an important role in plants, despite its precise function is unknown.

b) Subfamily PAObc2 was exclusively present in vascular plants included in these analyses (Fig. 5) suggesting that t-Spm oxidase activity might play an important role in the development of the vascular system.

c) The only TC-type PAO subfamily (subfamily PAOtc) was lost in Superasterids but it is present in all other land plants (Fig. 5). This indicated that the TC-type reactions are fundamental for land plants and that their function could be taken over by other enzymes in Superasterids, a hypothesis that was already suggested in previous reports [49, 50].

As we stated at the introduction of this work, the plant PAO family showed heterogeneity in terms of reaction mode, substrate specificity, reaction products, subcellular localization and structural features. Therefore, we made an effort to enrich the sequence database, grouping and characterizing the sequences and defining plant PAO subfamilies in order to obtain a more homogeneous and accurate classification of this enzyme family. The plant PAO subfamilies proposed here revealed that this protein family is conformed, at least in part, by homogeneous groups in terms of reaction mode and structural features.

The assessment of the correct evolutionary relationship between proteins and the assignment of an individual sequence to a functional or evolutionary group requires rigorous and time-consuming phylogenetic analyses and the use of differential conserved protein motifs could be an alternative approach to reach this goal. The automatic assignment using differential conserved motifs for each plant PAO subfamily was found to be comparable to the assignment by rough clustering and phylogenetic analysis performed in this work (Table 4). Furthermore, OsPAO7 was assigned to subfamily PAOtc (Table 4). This was consistent with the overall characteristics of this subfamily, as OsPAO7 is an apoplasmic TC-type PAO (Table 1) [17]. On the contrary, CsPAO4 was not assigned to subfamily PAOtc as expected, given

that it has been characterized as a TC-type PAO. Instead, it was located in subfamily PAObc2 (Table 4), which is in agreement with the sequence similarity of the members of this subfamily and with the lack of introns in the gene sequence, a particular feature shared with AtPAO5 [14, 45]. A further analysis revealed that CsPAO4 can be better modeled using MmAPAO as template, and the model obtained revealed the absence of the *aromatic sandwich* and the presence of His instead of Glu in the active site (Additional file 1: Table S5). Therefore, these motifs might be a useful tool for the identification *from scratch* of new plant PAOs as long as in the future the plant PAO subfamilies proposed in this work proves to be an accurate classification.

Conclusion

The results presented in this work reveal that the plant PAO family is bigger than previously conceived and provides new information on sets of candidate plant PAO sequences offering a potential starting point for further experimental verifications. Besides, the models obtained through the structure modeling analysis revealed that the residue interacting with the N₅ of the substrate PA might be one of the factors determining the reaction mode of the enzyme. Future additions to the structural and enzymatic properties of plant PAOs from different subfamilies may provide the necessary information needed to further characterize these groups. As an overall, this work delineates important background information for future specific structure-function and evolutionary investigations and lay a foundation for the in depth characterization of each plant PAO subfamily.

Methods

Domain architecture analysis

Domain architecture of all the currently well-documented PAO sequences was performed. ZmPAO1 (UniprotKB ID O64411), FMS1 (P50264), MmAPAO (Q8C0L6), AtPAO1 to 5 (Q9FNA2, Q9SKX5, Q9LYT1, Q8H191 and Q9SU79), OsPAO1 (Q5NAI7), OsPAO3 to 5 (Q7X809, Q7XR46 and Q0J954), OsPAO7 (Q0J290), BdPAO 2 and 3 (I1J1Z5 and I1J380), GhPAO5 (IDL7VGD5), SynPAO (*Cyanobacterium synechocystis* PAO; Q6ZEN7) and BjPAO (*Braquiosstoma japonicum* PAO; A0A059VBM4) were chosen since their kinetic properties, substrate specificity and reaction mode were well documented [9–21, 47, 53]. The protein sequences were scanned against the Pfam domain database using hmmscan software from the HMMER web server (<http://www.hmmer.org/>). Complete sequences were analyzed not excluding regions that were not assigned to any domains.

Data collection and database construction

An amino acidic sequence database based on the peptides domain architecture was constructed. In this regard,

peptides sequences with a single *Amino_oxidase* domain (PF01593) and no other domains were selected from the PFAM database. Protein sequences with other domain architectures containing the *Amino_oxidase* domain and other extra domains are known to have functions different from PAO, and no PAOs have been reported containing other extra domains (i.e. plant lysine histone demethylases possess an extra SWIRM domain) [54, 55]. Sequences from angiosperms and other early divergent green plant species were retrieved and filtered with the following selection criteria based on the domain architecture analysis:

1. Less or equal to 50 amino acids missing on any side of the *Amino_oxidase* domain.
2. No s gap with less or equal than 150 amino acids long.
3. At least five amino acids before the start and five amino acids after the end of the *Amino_oxidase* domain (to avoid truncated sequences).
4. No more than 700 amino acids in length (to exclude proteins with additional domains that could not be currently identified by the Pfam software).

With the purpose of improving the taxonomic representation, the genome of the recently sequenced fern *Azolla filiculoides* was searched for protein sequences that matched the PAO domain architecture using the stand alone version of the HMMER software. Sequences that passed the selection criteria were added to the database.

Global alignment and rough clustering

Sequences were aligned using the MAFFT online service [56], with a gap opening penalty of five. The resulting alignment was then manually adjusted and ambiguously aligned flanking regions were trimmed before subsequent clustering analysis.

For the rough clustering, a distance method (UPGMA) was used to construct a distance tree. Nodes separated by accumulative branch length less than 0.3 were considered to belong to the same cluster.

Search for sequences annotated as a different enzyme other than PAOs

Sequences within the database were used to perform a search in UniprotKB. IDs with a annotated status of “Reviewed” were selected to perform a manual search of the bibliography. Proteins other than PAOs whose activity was determined were considered as a different enzyme.

Prediction of subcellular localization

In order to predict subcellular localization of sequences within clades I to V, sequences were analyzed with a set of software using the standard configuration for plant protein sequences: SignalP 4.1 (cbs.dtu.dk/services/SignalP/), WoLF PSORT (wolfpsort.hgc.jp), LOCALIZER

(localizer.csiro.au/), slplocal2 (sunflower.kuicr.kyoto-u.ac.jp/~smatsuda/slplocal.html), DeepLoc1.0 (cbs.dtu.dk/services/DeepLoc/), PredSL (aias.biol.uoa.gr/PredSL/), TargetP1.1 (cbs.dtu.dk/services/TargetP/) and Pprowler (bioinf.scmb.uq.edu.au:8080/pprowler_webapp_1-2/).

Protein structure homology-modeling of plant PAOs

Three new alignments were made for each individual cluster including in each one the sequences of one of the three PAOs with known structure. Then, each sequence from the individual clusters was modeled using the ZmPAO1 (pdb code 3KU9), FMS1 (pdb code 1XPQ) and MmAPAO (pdb code 5MBX) structures as templates. For this, the *alignment mode* module from the SWISS-MODEL server was used (<https://swissmodel.expasy.org/>), with the corresponding alignment. Model quality parameters and *.pdb* files were retrieved. Although models with absolute QMEAN Z-score > 4 are considered to be of low quality [57] we decided to use a more lax criteria as the template for some models was taxonomically distant from the sequence to model. Models with more than 4.5 of absolute QMEAN Z-Score or less than 0.6 of GMQE were considered to be of low quality. Clusters whose sequences could not be modeled with any of the three templates (i.e. models obtained for every sequence were of low quality) were considered not belonging to plant PAO subfamilies.

Phylogenetic analyses

PAO sequences from the green plant lineages Charophytas, Bryophytes, Lycopodiophyta, Monilophyta, and Gymnosperms, as well as respective sequences from *A. trichopoda*, the single living representative from the sister lineage to all other angiosperms, were incorporated into the dataset to increase the breadth of our taxonomic sampling within angiosperms. These sequences were retrieved and filtered from Pfam with the same criteria used on the construction of the database. A second round of alignments was performed with MAFFT online service, now with a gap opening penalty of three. The resulting alignments were then manually adjusted and ambiguously aligned regions were trimmed before subsequent analyses. The best fitting model of substitution was selected with PartitionFinder 2 [58]. Maximum Likelihood was used for phylogenetic reconstructions with the program RAxML HPC2 version 8.2.9 [59], applying the “rapid Bootstrap and search for best-scoring ML tree” algorithm.

Structure analysis and active site amino acidic profiles

A multi-sequence structural analysis was carried out using the models obtained with the most suitable template for each subfamily. For this, the models obtained with the template that more frequently prompted the

higher modeling quality parameters were selected for each subfamily and analyzed using the Multiseq module of the VMD software [60], applying the Stamp Structure Alignment tool.

The individual residues and its proposed equivalents were selected for analyzing based on previously published works [21, 24, 25, 36, 37].

Differential conserved motifs identification

Motif search for automatic classification of plant PAOs were performed by using PRATT tool from Expasy Bioinformatic Resource Portal (expasy.org/PRATT) using the aligned sequences for each plant PAO subfamily. Sequence scanning against motifs was carried out using the Scanprosite program (expasy.org/tools/scanprosite). Sequences of recent reports of plant PAOs not included on this work were used to test the automatic classification of plant PAOs by aminoacidic motif search.

Additional file

Additional file 1: Figure S1. Domain Architecture of well-documented plant PAOs. **Table S1.** Percentages of identity between some of the well-documented plant PAOs. **Table S2.** Model quality parameters of models. **Table S3.** Prediction of subcellular localization. **Table S4.** Plant PAOs active site analysis. **Table S5.** CsPAO4 model quality and active site analysis. (PDF 12183 kb)

Abbreviations

AtPAO1–5: *Arabidopsis thaliana* PAO 1–5; BC: back conversion; BdPAO2 and BdPAO3: *Brachypodium distachyon* PAO 2 and PAO 3; CsPAO4: *Citrus sinensis* PAO 4; DAP: 1,3-diaminopropane; FMS1: *Saccharomyces cerevisiae* PAO; GhPAO5: *Gossypium hirsutum* PAO 5; HMM: Hidden markov model; MmAPAO: *Mus musculus* N1-acetyl PA oxidase; MmSMO: *M. musculus* spermine oxidase; *Oryza sativa* PAO 1–7; OsPAO1–7; PAOs: polyamine oxidases; PAs: polyamines; Put: putrescine; Spd: spermidine; Spm: spermine; TC: terminal catabolism; ZmPAO1: *Zea mays* PAO 1

Acknowledgements

We want to thank Dr. Gerrit T. S. Beemster and Dr. Han Asard from the Department of Biology of the University of Antwerp for valuable discussions and useful suggestions.

Funding

This work was supported by the Consejo Nacional de Investigaciones Científicas y Técnicas (CONICET, PIP 0411) and by Agencia Nacional de Promoción Científica y Técnica (ANPCyT, PICT2013/0477).

Availability of data and materials

All data generated or analyzed during this study are included in this published article and its supplementary information files.

Authors' contributions

CDB gathered the database, performed the distance rough clustering, performed and interpreted the protein homology modeling analysis and the differential conserved motifs identification. CGM performed the global alignment and performed and interpreted the phylogenetic analyses. CDB, CGM, JFGB, AG and AAR were major contributors in writing the manuscript. All authors read and approved the final manuscript.

Ethics approval and consent to participate

Not applicable.

Consent for publication

Not applicable.

Competing interests

Not applicable.

Publisher's Note

Springer Nature remains neutral with regard to jurisdictional claims in published maps and institutional affiliations.

Author details

¹Laboratorio de Fisiología de Estrés Abiótico en Plantas, Unidad de Biotecnología, INTECH - CONICET - UNSAM, Intendente Marino KM 8.2 - B7130IWA Chascomús, Buenos Aires, Argentina. ²Departamento de Botánica, Instituto de Biología, Universidad Nacional Autónoma de México, Apartado Postal 70-367, Coyoacán, 04510 México City, Mexico. ³División de Biología Molecular, Instituto Potosino de Investigación Científica y Tecnológica (IPICYT), San Luis Potosí, Mexico.

Received: 24 August 2018 Accepted: 14 January 2019

Published online: 21 January 2019

References

- Cohen SS. Guide to the polyamines. Oxford: Oxford University Press; 1998.
- Cona A, Rea G, Angelini R, Federico R, Tavladoraki P. Functions of amine oxidases in plant development and defence. *Trends Plant Sci.* 2006;11:80–8.
- Kaur-Sawhney R, Tiburcio AF, Altabella T, Galston AW. Polyamines in plants: an overview. *J Cell Mol Biol.* 2003;2:1–12.
- Bais HP, George J, Ravishankar G. Influence of polyamines on growth of hairy root cultures of witloof chicory (*Cichorium intybus* L cv Lucknow local) and formation of coumarins. *J Plant Growth Regul.* 1999;18:33–7.
- Rodríguez AA, Grunberg KA, Taleisnik EL. Reactive oxygen species in the elongation zone of maize leaves are necessary for leaf extension. *Plant Physiol.* 2002;129(4):1627–32.
- Steiner N, Santa-Catarina C, Silveira V, Floh EIS, Guerra MP. Polyamine effects on growth and endogenous hormones levels in *Araucaria angustifolia* embryogenic cultures. *Plant Cell Tiss Org.* 2007;89:55–62.
- Rodríguez AA, Maiale SJ, Menéndez AB, Ruiz OA. Polyamine oxidase activity contributes to sustain maize leaf elongation under saline stress. *J Exp Bot.* 2009;60(15):4249–62.
- Jiménez Bremont JF, Marina M, Guerrero-González MDLL, Rossi FR, Sánchez-Rangel D, Rodríguez-Kessler M, Gárriz A. Physiological and molecular implications of plant polyamine metabolism during biotic interactions. *Front Plant Sci.* 2014;5:95.
- Federico R, Angelini R, Cona A, Niglio A. Polyamine oxidase bound to cell walls from *Zea mays* seedlings. *Phytochemistry.* 1992;31:2955–7.
- Tavladoraki P, Rossi MN, Saccuti G, Perez-Amador MA, Politicelli F, Angelini R, Federico R. Heterologous expression and biochemical characterization of a polyamine oxidase from *Arabidopsis* involved in polyamine back conversion. *Plant Physiol.* 2006;141:1519–32.
- Kamada-Nobusada T, Hayashi M, Fukazawa M, Sakakibara H, Nishimura M. A putative peroxisomal polyamine oxidase AtPAO4 is involved in polyamine catabolism in *Arabidopsis thaliana*. *Plant Cell Physiol.* 2008;49:1272–82.
- Moschou PN, Sanmartin M, Andriopoulou AH, Rojo E, Sanchez-Serrano JJ, Roubelakis-Angelakis KA. Bridging the gap between plant and mammalian polyamine catabolism: a novel peroxisomal polyamine oxidase responsible for a full back-conversion pathway in *Arabidopsis*. *Plant Physiol.* 2008;147:1845–57.
- Ono Y, Kim DW, Watanabe K, Sasaki A, Niitsu M, Berberich T, Kusano T, Takahashi Y. Constitutively and highly expressed *Oryza sativa* polyamine oxidases localize in peroxisomes and catalyze polyamine back conversion. *Amino Acids.* 2012;42:867–76.
- Kim DW, Watanabe K, Murayama C, Izawa S, Niitsu M, Michael AJ, Berberich T, Kusano T. Polyamine oxidase 5 regulates *Arabidopsis thaliana* growth through a thermospermine oxidase activity. *Plant Physiol.* 2014;165:1575–90.
- Liu T, Kim DW, Niitsu M, Berberich T, Kusano T. *Oryza sativa* polyamine oxidase 1 back-converts tetraamines spermine and thermospermine to spermidine. *Plant Cell Rep.* 2014a;33:143–51.
- Liu T, Kim DW, Niitsu M, Maeda S, Watanabe M, Kamio Y, Berberich T, Kusano T. Polyamine oxidase 7 is a terminal catabolism-type enzyme in *Oryza sativa* and is specifically expressed in anthers. *Plant Cell Physiol.* 2014b;55:1110–22.

17. Mo H, Wang X, Zhang Y, Zhang G, Zhang J, Ma Z. Cotton polyamine oxidase is required for spermine and camalexin signalling in the defence response to *Verticillium dahliae*. *Plant J*. 2015;83:962–75.
18. Sagor GHM, Kusano T, Berberich T. Identification of the actual coding region for polyamine oxidase 6 from rice (*Oryza sativa*) and its partial characterization. *Plant Signal Behav*. 2017;12:e1359456.
19. Takahashi Y, Ono K, Akamine Y, Asano T, Ezaki M, Mouri I. Highly-expressed polyamine oxidases catalyze polyamine back conversion in *Brachypodium distachyon*. *J Plant Res* 2017;0:0.
20. Federico R, Cona A, Angelini R, Schinina ME, Giartosio A. Characterization of maize polyamine oxidase. *Phytochemistry*. 1990;29:2411–4.
21. Sjögren T, Wassvik CM, Snijder A, Aagaard A, Kumanomidou T, Barlund L, Kaminski TP, Kashima A, Yokota T, Fjellström O. The structure of murine N¹-acetylspermine oxidase reveals molecular details of vertebrate polyamine catabolism. *Biochemistry*. 2017;56:458–67.
22. Augeri MI, Angelini R, Federico R. Subcellular-localization and tissue distribution of polyamine oxidase in maize (*Zea-mays* L) seedlings. *J Plant Physiol*. 1990;136:690–5.
23. Slocum RD, Furey MJ. Electron-microscopic cytochemical localization of diamine and polyamine oxidases in pea and maize tissues. *Planta*. 1991;183:443–50.
24. Bianchi M, Polticelli F, Ascenzi P, Botta M, Federico R, Mariottini P, Cona A. Inhibition of polyamine and spermine oxidases by polyamine analogues. *FEBS J*. 2006;273:1115–23.
25. Fiorillo A, Federico R, Polticelli F, Boffi A, Mazzei F, Di Fusco M, Ilari A, Tavladoraki P. The structure of maize polyamine oxidase K300M mutant in complex with the natural substrates provides a snapshot of the catalytic mechanism of polyamine oxidation. *FEBS J*. 2011;278:809–21.
26. Huang Q, Liu Q, Hao Q. Crystal structures of Fms1 and its complex with spermine reveal substrate specificity. *J Mol Biol*. 2005;348:951–9.
27. Cheng Y, Vujcic S, Liang P, Diegelman P, Kramer DL, Porter CW. Genomic identification and biochemical characterization of a second spermidine/spermine N1-acetyltransferase. *Biochem J*. 2003;373:661–7.
28. Tavladoraki P, Cervelli M, Antonangeli F, Minervini G, Stano P, Federico R, Mariottini P, Polticelli F. Probing mammalian spermine oxidase enzyme-substrate complex through molecular modeling site-directed mutagenesis and biochemical characterization. *Amino Acids*. 2011;40:1115–26.
29. Cervelli M, Cona A, Angelini R, Polticelli F, Federico R, Mariottini P. A barley polyamine oxidase isoform with distinct structural features and subcellular localization. *Eur J Biochem*. 2001;268:3816–30.
30. Liu T, Wook Kim D, Niitsu M, Berberich T, Kusano T. POLYAMINE OXIDASE 1 from rice (*Oryza sativa*) is a functional ortholog of Arabidopsis POLYAMINE OXIDASE 5. *Plant Signal Behav*. 2014c;9:e29773.
31. Janin J, Chothia C. Domains in proteins: definitions, location and structural principles. *Method Enzymol*. 1985;115:420–30.
32. Finn RD, Coghill P, Eberhardt RY, Eddy SR, Mistry J, Mitchell AL, Potter SC, Punta M, Qureshi M, Sangrador-Vegas A, Salazar GA, Tate J, Bateman A. The Pfam protein families database: towards a more sustainable future. *Nucleic Acids Res*. 2016;44:D279–85.
33. Angelini R, Federico R, Bonfante P. Maize polyamine oxidase: antibody production and ultrastructural localization. *J Plant Physiol*. 1995;145:686–92.
34. Takahashi Y, Cong R, Sagor GHM, Niitsu M, Berberich T, Kusano T. Characterization of five polyamine oxidase isoforms in *Arabidopsis thaliana*. *Plant Cell Rep*. 2010;29:955–65.
35. Fincato P, Moschou PN, Spedaletti V, Tavazza R, Angelini R, Federico R, Roubelakis-Angelakis KA, Tavladoraki P. Functional diversity inside the Arabidopsis polyamine oxidase gene family. *J Exp Bot*. 2011;62:1155–68.
36. Polticelli F, Basran J, Faso C, Cona A, Minervini G, Angelini R, Federico R, Scrutton NS, Tavladoraki P. Lys300 plays a major role in the catalytic mechanism of maize polyamine oxidase. *Biochemistry*. 2005;44:16108–20.
37. Binda C, Coda A, Angelini R, Federico R, Ascenzi P, Mattevi A. A 30 Å long U-shaped catalytic tunnel in the crystal structure of polyamine oxidase. *Structure*. 1999;7:265–76.
38. Eom SH, Lee JK, Kim DH, Kim H, Jang KI, Ryu H, Hyun TK. Identification and expression profiling of flax (*Linum usitatissimum* L) polyamine oxidase genes in response to stimuli. *Acta Bot Croat*. 2017.
39. Wang W, Liu JH. CsPAO4 of *Citrus sinensis* functions in polyamine terminal catabolism and inhibits plant growth under salt stress. *Sci Rep*. 2016;6:31384.
40. Karplus K, Barrett C, Hughey R. Hidden Markov models for detecting remote protein homologies. *Bioinformatics*. 1998;14:846–56.
41. Park J, Karplus K, Barrett C, Hughey R, Haussler D, Hubbard T, Chothia C. Sequence comparisons using multiple sequences detect three times as many remote homologues as pairwise methods. *J Mol Biol*. 1998;284:1201–10.
42. Björklund ÅK, Ekman D, Light S, Frey-Skött J, Elofsson A. Domain rearrangements in protein evolution. *J Mol Biol*. 2005;353:911–23.
43. Chothia C, Lesk AM. The relation between the divergence of sequence and structure in proteins. *EMBO J*. 1986;5:823–6.
44. Kitashiba H, Honda C, Moriguchi T. Identification of polyamine oxidase genes from apple and expression analysis during fruit development and cell growth. *Plant Biotechnol*. 2006;23:425–9.
45. Wang W, Liu J. Genome-wide identification and expression analysis of the polyamine oxidase gene family in sweet orange (*Citrus sinensis*). *Gene*. 2015;555:421–9.
46. Cheng XQ, Zhu XF, Tian WG, Cheng WH, Sun J, Jin SX, Zhu HG. Genome-wide identification and expression analysis of polyamine oxidase genes in upland cotton (*Gossypium hirsutum* L). *Plant Cell Tiss Org*. 2017;129:237–49.
47. Samsil K, Lopes de Carvalho L, Mäenpää P, Salminen TA, Incharoensakdi A. Biochemical characterization and homology modeling of polyamine oxidase from cyanobacterium *Synechocystis* sp PCC 6803. *Plant Physiol Bioch*. 2017;119:159–69.
48. Igamberdiev AU, Lea PJ. The role of peroxisomes in the integration of metabolism and evolutionary diversity of photosynthetic organisms. *Phytochemistry*. 2002;60(7):651–74.
49. Tavladoraki P, Cona A, Angelini R. Copper-containing amine oxidases and FAD-dependent polyamine oxidases are key players in plant tissue differentiation and organ development. *Front Plant Sci*. 2016;7:824.
50. Campestre MP, Bordenave CD, Origone AC, Menéndez AB, Ruiz OA, Rodríguez AA, Maiale SJ. Polyamine catabolism is involved in response to salt stress in soybean hypocotyls. *J Plant Physiol*. 2011;168:1234–40.
51. Amborella genome project. The *Amborella* genome and the evolution of flowering plants. *Science*. 2013;1241089:342.
52. Alix K, Gérard PR, Schwarzacher T, Heslop-Harrison JS. Polyploidy and interspecific hybridization: partners for adaptation, speciation and evolution in plants. *Ann Bot-London*. 2017;120:183–94.
53. Wang H, Liu B, Li H, Zhang S. Identification and biochemical characterization of polyamine oxidases in amphioxus: implications for emergence of vertebrate-specific spermine and acetylpolyamine oxidases. *Gene*. 2016;575:429–37.
54. Spedaletti V, Polticelli F, Capodaglio V, Schinina ME, Stano P, Federico R, Tavladoraki P. Characterization of a lysine-specific histone demethylase from *Arabidopsis thaliana*. *Biochemistry*. 2008;47(17):4936–47.
55. Prakash S, Singh R, Lodhi N. Histone demethylases and control of gene expression in plants. *Cell Mol Biol*. 2014;60(5):97–105.
56. Katoh K, Standley DM. MAFFT multiple sequence alignment software version 7: improvements in performance and usability. *Mol Biol Evol*. 2013;30:772–80.
57. Benkert P, Biasini M, Schwede T. Toward the estimation of the absolute quality of individual protein structure models. *Bioinformatics*. 2011;27:343–50.
58. Lanfear R, Frandsen PB, Wright AM, Senfeld T, Calcott B. PartitionFinder 2: new methods for selecting partitioned models of evolution for molecular and morphological phylogenetic analyses. *Mol Biol Evol*. 2017;34:772–3 <https://doi.org/10.1093/molbev/msw260>.
59. Stamatakis A. RAxML version 8: a tool for phylogenetic analysis and post-analysis of large phylogenies. *Bioinformatics*. 2014;30(9):1312–3.
60. Humphrey W, Dalke A, Schulten K. VMD: visual molecular dynamics. *J Mol Graph*. 1996;14:33–8.
61. Gitzendanner MA, Soltis PS, Wong GK-S, Ruhfel BR, Soltis DE. Plastid phylogenomic analysis of green plants: a billion years of evolutionary history. *Am J Bot*. 2018;105:291–301 <https://doi.org/10.1002/ajb2.1048>.